

## Columbia County Highway V, Project Fact Sheet

### Location

The project is located on County Highway V (CTH V) beginning at State Highway 113 (STH 113) and ending at County Highway J (CTH J). The total project length is approximately 4 miles.

### Proposed Improvements

The project includes reconstructing CTH V from STH 113 to Red Cedar Drive as a two-lane urban roadway section with curb and gutter. The remaining segment of CTH V from Red Cedar Drive to CTH J will be reconstructed as a two-lane rural roadway section including pavement replacement and shoulder widening. Project also includes replacing the existing bridge spanning Lake Wisconsin.

### Project Considerations (STH 113 – Red Cedar Drive)

- Public involvement
- Intersection sight distance at STH 113
- Vertical profile at railroad crossing
- Horizontal curve at Shamrock Road
- Substandard shoulder widths
- Drainage
- Uncontrolled driveway access
- Divert CTH V onto Shamrock Road
- Navigational clearance under bridge
- Bicycle and pedestrian facilities
- Fishing access
- Environmental agency coordination
- Construction scheduling
- Access during construction
- Parking
- Minimize impacts to adjacent property

### Project Considerations (Red Cedar Drive – CTH J)

- Public involvement
- Lane and shoulder widths
- Ryan Road Intersection
- Vertical roadway profile
- CTH J intersection safety
- Minimize impacts to adjacent property

### Estimated Project Construction Costs

Roadway	\$5,350,000
Bridge	\$ 475,000

### Questions/Comments

If you have any questions or comments regarding this project contact:

Eric Sorensen, PE, Project Manager  
Ayres Associates Inc  
3433 Oakwood Hills Parkway  
Eau Claire, WI 54702-1590  
715.834.3161  
[SorensenE@AyresAssociates.com](mailto:SorensenE@AyresAssociates.com)

For more information, please visit the project website at [www.columbiacountyv.com](http://www.columbiacountyv.com).